

Volume 2, Issue 2

Research Article

Date of Submission: 01 April, 2025

Date of Acceptance: 28 April, 2025

Date of Publication: 15 May, 2025

A Systematic Study of Sustainable Contemporary Synthesis of Modular and Site-Built Construction from Factory to Field Delivery

Vinayak Kaushal* and Jainil Patel

Civil Engineering Department, The University of Texas at Arlington, Arlington, Texas

Corresponding Author:

Vinayak Kaushal, Civil Engineering Department, The University of Texas at Arlington, Arlington, Texas.

Citation: Kaushal, V., Patel, J. (2026). A Systematic Study of Sustainable Contemporary Synthesis of Modular and Site-Built Construction from Factory to Field Delivery, *Infra Tech J Sustain Archit Civ Eng*, 2(2), 01-05.

Abstract

Rapid urbanization and the urgency to curb climate impacts have driven the construction industry to seek methods that deliver efficiency without compromising sustainability. Traditional on-site construction often struggles with extended timelines, resource inefficiencies, and significant environmental burdens. Modular construction—an approach that shifts substantial portions of building production to controlled factory settings—offers a promising alternative. This paper studies modular construction in contrast to conventional site-built methods, highlighting its sustainability potential to accelerate project delivery, improve quality control, and reduce waste and emissions. Further, this study incorporates an original synthesis contrasting modular (volumetric and panelized) delivery with conventional site-built methods. It organizes evidence and guidance across decision sequencing, product-platform design, logistics, risk allocation, and lifecycle performance, with pragmatic selection criteria and implementation checklists. While modular construction is not a universal solution, evidence suggests that, when applied under appropriate conditions, it can substantially enhance performance and sustainability outcomes. The discussion emphasizes environmental considerations, operational advantages, and strategic factors that influence successful implementation, positioning modular construction as a key contributor to the future of resilient and resource-efficient building practices. Recent market intelligence, policy updates, and schematic diagrams for decision flow, logistics constraints, and design-freeze governance are also discussed based on the findings.

Keywords: Sustainability, Modular Construction, Volumetric Modules, Panelized Systems, Off-Site, Industrialized Construction, Decision Governance, Logistics, Lifecycle

Introduction

Industrialized construction continues to mature as a credible alternative to entirely site-based production. Modularization shifts repetitive, tolerance-critical work to factories and leaves site activities focused on foundations, cranes, and utility integration. Recent industry analyses underscore both the potential and the caveats: adoption is rising but remains single-digit market share in North America; firms that control their value chain and standardize around strong building systems tend to outperform. [1,2].

This systematic study critically compares modular construction with conventional site-built methods, emphasizing its sustainability potential to accelerate project delivery, enhance quality control, and minimize waste and emissions based on the literature from the last more than 15 years. It presents an original synthesis of modular typologies—volumetric and panelized—against traditional approaches, organizing evidence and guidance across decision sequencing, product-platform design, logistics, risk allocation, and lifecycle performance. Practical selection criteria and implementation checklists are provided, alongside recent market insights, policy developments, and author-developed schematics

illustrating decision flows, logistics constraints, and design-freeze governance derived from the literature review.

Typologies of Modular Delivery

Organizationally, modular delivery spans relocatable (temporary) and permanent installations. Physically, it manifests as panelized (2D) elements, volumetric (3D) units, and hybrids (e.g., volumetric cores with panelized facades). Regulatory acceptance has accelerated in several jurisdictions—e.g., Hong Kong’s MiC pre-acceptance mechanisms and government circulars—to streamline approvals and transport permits for oversize modules. (Buildings Department 2025) [3,4].

Stakeholders and Decision Sequencing

Modular adds manufacturer/dealer roles alongside owners, designers, and constructors. The “go/no-go” decision should be made during feasibility, when typology fit, factory capacity, logistics feasibility, regulatory context, and team experience can be evaluated. Integrated models (design-build, IPD) often align better with early design definition and configuration control. Public policy roadmaps (HUD/NIBS 2023) similarly emphasize contracts, finance, and workforce as enablers. (NIBS 2025; HUD/NIBS 2023).

Figure 1 shows modular delivery decision flow.




Figure 1: Modular Delivery Decision Flow

Process Overview

Under modular delivery, design advances to a higher level of definition before fabrication. Factory production proceeds concurrently with site works, migrating inspection and testing upstream. Logistics (routes, permits, cranage, laydown) can become the critical path; proactive planning of windowed constraints is essential to avoid idle modules or site crews. [3,4]. Figure 2 shows logistics constraints over pre-assembly window.




Figure 2: Logistics Constraints Over Pre-Assembly Window

Comparative Benefits and Trade-offs

Schedule

Concurrent factory and site work, repeatable assembly, and reduced weather exposure can compress delivery, provided configuration freeze is enforced. [1].

Quality and Rework

Factory workflows improve consistency and traceability but can propagate unmitigated design errors; rigorous preproduction reviews are mandatory. [5].

Safety

Shifting hazardous tasks to controlled settings reduces exposure to falls and site congestion; nonetheless, craning and lifting require specialized plans. (BLS 2025) [6].

Risk Allocation

Interfaces must be explicit across design–manufacture–install, with performance criteria for modules, transport, and set-out. (HUD/NIBS 2023).

Sustainability Environment Considerations

Lifecycle impacts hinge on factory energy mix, transport distances/modes, material choice, and site operations. Empirical studies report reductions in on-site emissions and waste, though transport and plant energy can offset gains depending on context. Recent comparative LCA from Hong Kong indicates ~22% GHG reduction during construction for MiC versus conventional counterparts, with embodied materials dominating both [7,8].

Where Modular Adds Value

Modular is compelling for repeatable programs (rooms, labs, classrooms), hard occupancy dates, constrained sites (dense urban or remote), and climates limiting construction seasons. Market data show growth in multifamily, education, and government facilities; value improves when firms standardize on one primary material and exercise tighter value-chain control [1,2].

Decision Guide and Checklists

Use the following checklists to structure early decisions and de-risk implementation:

- **Typology Fit:** Repetition level; tolerance requirements; spans vs. transport constraints.
- **Factory & Product Platform:** Proven capacity; QA certifications; module envelope; standardized interfaces.
- **Logistics & Permits:** Route surveys; wide-load permits; craning windows; staging/laydown; just-in-time delivery plans.
- **Regulatory Path:** Pre-acceptance mechanisms; code equivalence; inspection regimes.
- **Delivery Model & Contracts:** DB/IPD suitability; interface matrices; performance specs for modules and transport.
- **Team Experience:** Manufacturer track record; integrator capabilities; commissioning expertise.
- **Environmental Context:** Factory energy mix; waste policy; LCA boundary settings.
- **Finance & Risk:** Demand certainty; capacity utilization; contingency tied to logistics and design-freeze governance.

Figure 3 shows design-freeze timeline and parallel workstreams.




Figure 3: Design-Freeze Timeline and Parallel Workstreams

Implementation, Conclusions and Recommendations

Based on the synthesis of results, the governance mechanisms should explicitly protect configuration stability: define freeze gates, change-control boards, and cost-of-change curves; align procurement and manufacturing slots; and ensure digital coordination (BIM) across design–manufacture–install. Public sector policies (e.g., Hong Kong DEVB circulars) demonstrate how mandates accelerate adoption while standardizing compliance pathways. (BD 2025) [4].

Modular construction demonstrates clear advantages over traditional on-site methods, offering faster delivery, cost efficiencies, and measurable sustainability/environmental benefits through reduced waste and improved resource utilization. Its factory-based approach enhances quality control and makes it particularly suitable for high-rise and complex projects where precision and scheduling are critical. While modular construction is not a universal solution, its strategic application can significantly transform industry practices and accelerate progress toward sustainability goals. To fully realize its potential, stakeholders must adopt robust governance frameworks, enforce design-freeze discipline, and leverage digital tools such as BIM and life-cycle assessment for informed decision-making.

To advance modular construction as a mainstream solution, future studies should focus on:

- **Life-Cycle Environmental Assessment:** Conduct comprehensive LCAs across diverse building typologies and climates to quantify carbon savings and resource efficiency.
- **Integration of Digital Technologies:** Explore interoperability between BIM, LCA, and supply-chain platforms to enable real-time decision-making and predictive analytics.
- **Policy and Regulatory Frameworks:** Assess the effectiveness of modular-friendly codes, permitting processes, and incentives in accelerating adoption globally.
- **Economic and Social Impact Analysis:** Investigate cost-benefit trade-offs, workforce implications, and community acceptance to ensure equitable and scalable implementation.
- **Design for Circularity:** Develop guidelines for modular components that support reuse, recycling, and design-for-disassembly principles to close material loops.
- **Performance in Extreme Conditions:** Examine modular resilience under seismic, hurricane, and flood scenarios to validate safety and durability standards.

By addressing these research priorities, the construction industry can strengthen the evidence base for modular solutions and ensure their alignment with long-term sustainability and resilience objectives.

References

1. Sjödin, E., and Chandrasekaran, S. (2025). 'Putting the pieces together: Unlocking success in modular construction.' McKinsey & Company, (accessed December 28, 2025).
2. Modular Building Institute. (2025). 'Modular Construction Reports & Industry Analysis.'
3. Construction Industry Council (Hong Kong). (2023). Statutory Requirements for Modular Integrated Construction Projects.
4. Development Bureau (Hong Kong). (2024). Technical Circular (Works) No. 4/2024: Modular Integrated Construction

- (MiC).
5. NIBS and AIA. (2025). Modular and Off-Site Construction Guide.
 6. Occupational Safety and Health Administration (OSHA). (2025). Commonly Used Statistics.
 7. Wang, Y., Lam, S. K., Wu, Z., Gong, L., Li, H., & Jiang, M. (2025). Does the Modular Construction Project Outperform the Traditional One? A Comparative Life Cycle Analysis Study in Hong Kong. *Buildings*, 15(16), 2811.
 8. European Commission (HLCF Technical Secretariat). (2024). Research Note on Offsite Construction.
 9. Bertram, N., Fuchs, S., Mischke, J., Palter, R., Strube, G., & Woetzel, J. (2019). Modular construction: From projects to products. McKinsey & Company: Capital Projects & Infrastructure, 1(1), 1-34.
 10. Boafo, F. E., Kim, J. H., & Kim, J. T. (2016). Performance of modular prefabricated architecture: Case study-based review and future pathways. *Sustainability*, 8(6), 558.
 11. Building and Construction Authority. Code of practice on building design/ buildability, Singapore; (2017).
 12. Davies G. The future of DfMA is the future of construction. *Eng Excellence J* 2013: 1–77.
 13. Deluxe Modular. The differences between prefab and modular construction, from (2019).
 14. Generalova, E. M., Generalov, V. P., & Kuznetsova, A. A. (2016). Modular buildings in modern construction. *Procedia engineering*, 153, 167-172.
 15. Hardiman-Williams LLC. (2024). '2024 Modular Construction Annual Reports.' Offsite Construction Network.
 16. Harrison G. (2018) The future is prefabricated, from.
 17. Hořínková, D. (2021, November). Advantages and disadvantages of modular construction, including environmental impacts. In *IOP Conference Series: Materials Science and Engineering* (Vol. 1203, No. 3, p. 032002). IOP Publishing.
 18. Jellen A, Memari A. (2023). The state-of-the-art application of modular construction to multi-story residential building. *Proceedings of the 1st Residential Building Design & Construction Conference 2013*:284–293.
 19. Jiang, Y., Zhao, D., Wang, D., & Xing, Y. (2019). Sustainable performance of buildings through modular prefabrication in the construction phase: A comparative study. *Sustainability*, 11(20), 5658.
 20. Jin, R., Hong, J., & Zuo, J. (2020). Environmental performance of off-site constructed facilities: A critical review. *Energy and buildings*, 207, 109567.
 21. Kamali, M., & Hewage, K. (2016). Life cycle performance of modular buildings: A critical review. *Renewable and sustainable energy reviews*, 62, 1171-1183.
 22. Lawson, R. M., Grubb, P. J., Prewer, J., & Trebilcock, P. J. (1999). *Modular construction using light steel framing: an architect's guide*. SCI publication.
 23. McKinsey. (2019) *Modular construction: From projects to products*, from
 24. Mortice Z. (2019) Can this Chicago apartment factory make new homes affordable? from
 25. National Institute of Building Sciences (NIBS). (2025). Off-Site Construction Council (OSCC).
 26. Pan W, Hon CK. (2019). Modular integrated construction for high-rise buildings. *Proc Inst Civ Eng Munic Eng* 2019.
 27. Pan, W., Su, R., Cai, Y., & Young, B. (2018, November). Engineering modular systems for high-rise buildings: an update. In *Proceedings of the Institution of Civil Engineers-Civil Engineering* (Vol. 171, No. 4, pp. 148-148). Thomas Telford Ltd.
 28. Research and Markets. (2025). *Modular Construction – Global Strategic Business Report*.
 29. Zhang, R., Zhou, A. S., Tahmasebi, S., & Whyte, J. (2019, November). Long-standing themes and new developments in offsite construction: the case of UK housing. In *Proceedings of the Institution of Civil Engineers-Civil Engineering* (Vol. 172, No. 6, pp. 29-35). Thomas Telford Ltd.
 30. Shan, S., Looi, D., Cai, Y., Ma, P., Chen, M. T., Su, R., ... & Pan, W. (2019, November). Engineering modular integrated construction for high-rise building: a case study in Hong Kong. In *Proceedings of the Institution of Civil Engineers-Civil Engineering* (Vol. 172, No. 6, pp. 51-57). Thomas Telford Ltd.
 31. Smith, R. E. (2011). *Prefab architecture: A guide to modular design and construction*. John Wiley & Sons.
 32. Smith, R. E. (2016). *Off-site and modular construction explained*. National institute of building sciences.
 33. Smith, R. E., & Quale, J. D. (Eds.). (2017). *Offsite architecture: Constructing the future*. Taylor & Francis.
 34. Stern, D. (2017). *Steel-framed modular construction for high-rise hotels*.
 35. Thompson, J. (2019). *Modular construction: A solution to affordable housing challenges*.
 36. U.S. Bureau of Labor Statistics. (2025). 'Fatal falls in the construction industry in 2023.' *The Economics Daily*.
 37. Agenda, I. (2016, May). Shaping the future of construction a breakthrough in mindset and technology. In *World Economic Forum* (pp. 11-16).
 38. WRAP. Waste reduction potential of offsite volumetric construction. WAS 003- 003: Offsite Construction Case Study; 2018: 1–11.
 39. Yu, Y., & Chen, Z. (2018). Rigidity of corrugated plate sidewalls and its effect on the modular structural design. *Engineering Structures*, 175, 191-200.